# Lot 409 Arbor Green

Stage 17, Arbor Green, Springwood, Rolleston




## House & Land Package:

Family sized home featuring four bedrooms, master with ensuite, open plan kitchen living and dining, family bathroom and internal access garaging. Well appointed for the sun on a fully landscaped section, offering quality fixtures and fittings throughout.

**$769,900**

| | |
|---|---|
| **Home area:** | 156m² |
| **Section area:** | 405m² |

4 1 2 2


## Features:

- Turnkey
- Master Build 10-Year Guarantee
- 1 year warranty period
- Healthy Homes compliant
- RibRaft foundation
- Modern bathroomware
- Custom kitchen cabinetry
- Tri-Stone benchtop
- Window coverings
- Fully landscaped


**P:** (03) 977 2832
**E:** info@oakridgehomes.co.nz
**oakridgehomes.co.nz**


OAKRIDGE HOMES

# Floor Layout




# Site Location




**P:** (03) 977 2832
**E:** info@oakridgehomes.co.nz
**oakridgehomes.co.nz**

OAKRIDGE HOMES

# Specification

| General | | | |
|---|---|---|---|
| Guarantee: | Master Build 10-Year | Insurance: | Builders All Risk |
| Warranty | 1 year from settlement | Utilities: | Mains supply including fibre |
| **Dwelling Exterior** | | | |
| Foundation: | TC1 RibRaft | Framing / trusses: | 2.42m LVL |
| Roofing: | 10° longrun corrugate | Fascia and gutter: | Dimond metal fascia and quad gutter |
| Downpipes: | Colorsteel 75×55 rectangular | Main cladding: | Rockcote Graphex<br>(15yr manufacturers guarantee) |
| Feature cladding: | James Hardie Axon | Entry door: | APL 860mm Latitude with urbo lever |
| Window joinery: | Low E Argon filled double glazed windows in thermally-broken powder coated aluminium frames | Garage door: | Insulated Colorsteel flat panel woodgrain |
| **Dwelling Interior** | | | |
| Insulation: | As per Building Code. Including entire garage envelope - internal & external walls | Plasterboard: | Plasterboard - 10mm to walls, wet area to bathrooms and 13mm to ceilings |
| Gib stopping: | Grade 4 paint finish in accordance with AS/NZ 2311:2009 | External corners: | Square stop |
| Hinged doors: | 1980mm (horizontal V groove) | Wardrobe sliders: | 2200mm Horizontal V groove |
| Wardrobe shelving: | MDF shelf and rail | Cupboard shelving: | MDF shelves x4 |
| Door hardware: | Windsor Futura – Apex brushed nickel | Skirting board: | 60mm bevel |
| Electrical: | As per plan | Heatpump: | Fujitsu SET-ASTH22KNTA 6.0/6.5kw |
| Extractor: | Inline extractor fan & extractor duct as per electrical plan | Hot water cylinder: | Rheem 250L |
| Carpet: | Urban Collection - Inner Urban | Vinyl plank: | Belgotex Luxury Plank – Province |
| Kitchen, bench surface and splashback: | Custom made Melteca or Bestwood finished cabinetry. TriStone 30mm square edge benchtop. Tiled splashback full length of back bench/wall. | Window coverings: | Windoware Everyday Vinyl Collection – Mystic. Excluding garage & bathrooms |
| **Landscaping** | | | |
| Driveway and patio: | Exposed aggregate – sealed | Vehicle crossing: | Included |
| Soft landscaping: | As per plan | Fencing: | As per plan |

**P:** (03) 977 2832
**E:** info@oakridgehomes.co.nz
**oakridgehomes.co.nz**

OAKRIDGE HOMES

# Specification

## Kitchen and Laundry *Refer to plans and colour scheme

**Kitchen tapware:**

Elementi Uno Gooseneck



**Kitchen sink:**

Lazio NZLSS-5545 single stainless steel sink



**Oven:**

Bosch HBF133BSOA



**Kitchen handles:**

Stefano Orlati 4062— Titanium




**Powerpack:**

Bosch DHL755BAU



**Ceramic cooktop:**

Bosch PKE611K17A



**Laundry tub:**

Aquatica Laundra Studio

*dependent on supply, similar fitting to be used if unavailable



**Dishwasher:**

Bosch SMU2ITS01A



## Bathrooms

**Vanities:**

Elementi Novara, 2 drawer 750mm, French Oak




**Mirrors:**

Polished edge direct fix—1000×750mm



**Showers:**

Arena curved with moulded wall



**Toilets:**

Elementi Uno back to wall



**Bath:**

Elementi Diseno back-to-wall 1700mm



**Towel rails:**

Newtech 5 bar square—heated



**Basin mixers:**

Elementi Cura



**Shower / bath mixers:**

Elementi Cura



**Shower slides:**

Elementi Rayne



**Bath spout:**

Elementi Uno



**P:** (03) 977 2832
**E:** info@oakridgehomes.co.nz
**oakridgehomes.co.nz**

OAKRIDGE HOMES

# Colour Schedule


## Exterior Colours

| Colour Scheme | | | |
|---|---|---|---|
| **EXTERIOR** | | | |
| Roof: | Ebony | Garage door & frame: | Ebony |
| Fascia: | Ebony | Soffits: | Half black white |
| Gutter & downpipes: | Ebony | Exterior cladding (Main): | All black |
| Window joinery: | Ebony | Exterior cladding (Feature): | All black |
| Front door & frame: | Ebony | | |



## Interior Colours

| Colour Scheme | | | |
|---|---|---|---|
| **INTERIOR** | | | |
| Ceilings: | Half black white | Kitchen benchtop: | TriStone 30mm – Antarctic Snow |
| Walls: | Black white | Kitchen joinery main colour: | Carbon |
| Interior doors: | Black white | Kitchen joinery feature colour: | Southern oak |
| Skirting: | Black white | Kitchen splashback: | Mallorca White Gloss 50×250—vertical stack with misty grey grout |
| Carpet: | Shimmer | Feature pendant: | Elba 365 black |
| Vinyl plank: | Natural | | |



**P:** (03) 977 2832
**E:** info@oakridgehomes.co.nz
**oakridgehomes.co.nz**

OAKRIDGE HOMES

## General Notes

All dimensions shown are to *face of foundation* unless noted otherwise.

Refer to Foundation Plan for foundation setout.

Refer to Drainage Plan for specific drainage info.

Refer to Sediment Control in Specification & implement where required.

Driveway stormwater runoff to road when it does not flow over a footpath. Otherwise driveway stormwater runoff to be collected and disposed via soak pit located within property.


All sealed driveway and patio areas to be min. 1:100 fall away from building.

## Site Info

| | |
|---|---|
| Site Address | 55 Solihull Drive Rolleston |
| Legal Description | Lot 409 |
| Site Area | 405m² |
| Building Area | 156.59m² |
| Roof Area* | 186.62m² |
| Site Coverage | 46.08% |

## Design Basis

| | |
|---|---|
| Wind Zone | High |
| Earthquake Zone | 2 |
| Snow Zone | N4 < 100m |
| Exposure Zone | C |





Archiplus

6 Browns Road, Christchurch
ey.archiplus@gmail.com
021 0238 1905
021 0221 8868

LICENSED BUILDING PRACTITIONER
BUILDING CONFIDENCE


**W E N D E L B O R N P R O P E R T Y L T D**

L O T 4 0 9 A R B O R G R E E N
5 5 S O L I H U L L D R I V E R O L L E S T O N

**Issue**
Concept Design



This plan is developed for the purchaser and is copy right to Archiplus Ltd.


**Site Plan**

Scale 1:100 @ A3

Revision 2
Date 15/10/2026
File No. **26173**

**Sheet No.**
**1**




## Building Area

| | |
|---|---|
| Over Frame | 152.80m² |
| Perimeter | 57.34m |
| Over Cladding | 156.59m² |
| Perimeter | 57.82m |
| Roof Area* | 186.62m² |
| Perimeter | 58.90m |

*Roof area includes fascia & gutter.

## General

| | |
|---|---|
| Main Cladding | RCS Graphex |
| Feature Cladding | James Hardie Axon Panel |
| Roof Pitch | 10° |
| Roofing | Longrun Corrugated |
| Stud Height | 2.42m |
| Interior Door | 1.98m high |
| Wardrobe Door | 2.20m high |
| Cooktop | Ceramic Cooktop |

Note: Kitchen layout indicative only, refer to Kitchen Design for details.

## Legend

- Distribution Board & Smart Meterbox
- Data Box
- SD — Smoke Detector 10 year long-life battery-operated & interconnected

## Floor Covering

- Carpet (excl. Garage)
- Vinyl Planks

| WINDOW SCHEDULE | | |
|---|---|---|
| ID | H | W |
| w01 | 2,130 | 960 |
| w02 | 2,130 | 2,000 |
| w03 | 1,400 | 1,500 |
| w04 | 2,130 | 1,800 |
| w05 | 2,130 | 1,800 |
| w06 | 1,400 | 1,500 |
| w07 | 2,130 | 1,800 |
| w08 | 1,400 | 600 |
| w09 | 1,400 | 600 |
| w10 | 1,100 | 1,200 |
| w11 | 1,400 | 1,500 |
| w12 | 1,100 | 1,200 |
| w13 | 1,400 | 1,500 |
| w14 | 2,130 | 960 |

Archiplus
6 Browns Road, Christchurch
ey.archiplus@gmail.com
021 0238 1905
021 0221 8868
LICENSED BUILDING PRACTITIONER BUILDING CONFIDENCE

**W E N D E L B O R N P R O P E R T Y L T D**

L O T 4 0 9 A R B O R G R E E N
5 5 S O L I H U L L D R I V E R O L L E S T O N

**Issue**
Concept Design


This plan is developed for the purchaser and is copy right to Archiplus Ltd.

**Floor Plan**

Scale 1:100 @ A3

Revision 2
Date 15/10/2026
File No. **26173**

**Sheet No.**
**2**




## Roof Cladding

10º Colorsteel corrugate roofing over Covertek 215 roof underlay.

## Fascia & Gutter

Colorsteel Quad gutter supported on 185mm Colorsteel fascia.

## Downpipes

75x55mm Colorsteel downpipes with wall brackets.

## Roof Penetrations

Seal all pipe penetrations with Dektite flashing kit as per specification.

## Downpipe Catchment (Plan Area)

| | |
|---|---|
| d.p.1 | 35m² |
| d.p.2 | 35m² |
| d.p.3 | 22m² |
| d.p.4 | 44m² |
| d.p.5 | 44m² |

## Roof Bracings

Refer to truss design.

Archiplus
6 Browns Road, Christchurch
ey.archiplus@gmail.com
021 0238 1905
021 0221 8868
LICENSED BUILDING PRACTITIONER BUILDING CONFIDENCE

**W E N D E L B O R N P R O P E R T Y L T D**

L O T 4 0 9 A R B O R G R E E N
5 5 S O L I H U L L D R I V E R O L L E S T O N

**Issue**
Concept Design


This plan is developed for the purchaser and is copy right to Archiplus Ltd.

**Roof Plan**


Scale 1:100 @ A3

Revision 2
Date 15/10/2026
File No. **26173**


**Sheet No.**
**3**





E-01 NorthEast Elevation
Scale 1:100




E-02 NorthWest Elevation
Scale 1:100




E-03 SouthWest Elevation
Scale 1:100




E-04 SouthEast Elevation
Scale 1:100

## Elevation Keys

| | |
|---|---|
| C01 | RCS Graphex 50mm panel with plastered finish on 20mm cavity battens. |
| C02 | James Hardie Axon panel on 20mm cavity battens. |
| R01 | Colorsteel corrugate roofing. |
| R02 | Colorsteel Quad gutter supported by Colorsteel 185mm fascia. |
| R03 | Colorsteel 75x55mm downpipes. |
| J01 | Low E Argon filled double glazed windows in thermally-broken powder coated aluminium frames. |
| J02 | Sectional garage door. |
| J03 | APL entry door in thermally-broken powder coated aluminium frames. |
| S01 | Drainage vent pipe. |
| S02 | Heatpump outdoor unit on wall bracket. |

## Legend

| | |
|---|---|
| w01 | Window ID |
| SS | Security Stay |
| SG | Safety Glass |
| CJ | Control Joint |

## General Notes

Driveway to fall from 20mm max. below garage rebate.

Archiplus
6 Browns Road, Christchurch
ey.archiplus@gmail.com
021 0238 1905
021 0221 8868
LICENSED BUILDING PRACTITIONER BUILDING CONFIDENCE

**W E N D E L B O R N P R O P E R T Y L T D**

L O T 4 0 9 A R B O R G R E E N
5 5 S O L I H U L L D R I V E R O L L E S T O N

**Issue**
Concept Design


This plan is developed for the purchaser and is copy right to Archiplus Ltd.

**Elevations**


Scale 1:100 @ A3

Revision 2
Date 15/10/2026
File No. **26173**


**Sheet No.**
**4**




A Section A-A
Scale 1:50




B Section B-B
Scale 1:50




C Section C
Scale 1:50

## Section Keys

| | |
|---|---|
| C01 | RCS Graphex 50mm panel with plastered finish on 20mm cavity battens over building underlay on timber framing. |
| C02 | James Hardie Axon panel on 20mm cavity battens over building underlay on timber framing. |
| W01 | External walls 90x45mm studs @ 600mm crs, dwangs @ 800mm crs. Top plates 90x45 + 140x35mm. |
| W02 | External walls 140x45mm studs @ 600mm crs, dwangs @ 800mm crs. Top plates 140x45 + 140x35mm. |
| W03 | Internal walls 90x45mm studs @ 600mm crs, dwangs @ 800mm crs. |
| S01 | Ribraft floor slab and foundation. |
| T01 | Roof trusses as per Truss Design. |
| T02 | Extended truss top chords / purlins to form raking soffit, refer to Truss Design. |
| R01 | Colorsteel corrugate roofing over self-supported roof underlay on 70x45mm purlins on trusses. |
| R02 | Colorsteel Quad gutter on Colorsteel fascia. |
| R03 | 75x55mm Colorsteel downpipes with wall brackets. |
| J01 | Low E Argon filled double glazed windows in thermally-broken powder coated aluminium frames. H3.1 timber reveals for painted finish. |
| J02 | Sectional garage door. H3.1 timber reveals for painted finish. |
| B01 | R2.6 wall insulation batts. |
| B02 | 2 x R3.6 (165mm) double layer ceiling insulation batts. Single layer along the perimeter edge 250mm from the outer edge of top plate of Lounge / Dining / Family. |
| L01 | 4.5mm soffit linings for painted finish. |
| L02 | 13mm Gib ceiling linings supported by 35mm Rondo ceiling battens direct fixed @ 600mm crs. Stopped smooth for painted finish. (Wet area ceiling 13mm Gib Aqualine) |
| L03 | 10mm Gib wall linings stopped smooth for painted finish. (Wet area wall 10mm Gib Aqualine) |

Archiplus
6 Browns Road, Christchurch
ey.archiplus@gmail.com
021 0238 1905
021 0221 8868
LICENSED BUILDING PRACTITIONER BUILDING CONFIDENCE

**W E N D E L B O R N P R O P E R T Y L T D**

L O T 4 0 9 A R B O R G R E E N
5 5 S O L I H U L L D R I V E R O L L E S T O N

**Issue**
Concept Design


This plan is developed for the purchaser and is copy right to Archiplus Ltd.

**Cross Sections**

Scale 1:50 @ A3

Revision 2
Date 15/10/2026
File No. **26173**

**Sheet No.**
**5**






## Plants List for Garden Bed

Agapanthus Peter Pan - Dwarf blue Nile lily

Acacia Limelight - Dwarf wattle

Choisya Ternata - Mexican orange blossom

Carex Secta - Makura sedge

Lavandula angustifolia 'Hidcote' - English Lavender

Pittosporum little gem

Thuja occidentalis Smaragd - Emerald Cedar

Viburnum tinus Eve Price


Azalea

Corokia geentys green

Pseudowintera colorata 'Red Leopard' - Horopito/Pepper tree

Camellia 'Cinnmon Cindy'

*Planting species for garden bed are indicative-not to be limited to.




## Legends

Lawn

Exposed Aggregate

Stonechip

Garden Bed with Bark


Portuguese Laurel - Hedge to be a min. 800mm high at time of planting and a max of 600mm apart (stem to stem)

Tree - within 2m of road frontage. 2.5m high (at time of planting)

Macrocarpa posts 200x200mm with capping, supplied by Arbor Green. To be installed by Oakridge Homes. Mulseal and concrete encase posts, setback 900mm from road boundary and set off the driveway edge by 200mm

Timber Batten Edging

'Picket Panel Juno' fence in black



Fencing

Archiplus
6 Browns Road, Christchurch
ey.archiplus@gmail.com
021 0238 1905
021 0221 8868
LICENSED BUILDING PRACTITIONER
BUILDING CONFIDENCE

**W E N D E L B O R N P R O P E R T Y L T D**

L O T 4 0 9 A R B O R G R E E N
5 5 S O L I H U L L D R I V E R O L L E S T O N

**Issue**
Concept Design


This plan is developed for the purchaser and is copy right to Archiplus Ltd.

**Landscape Plan**

Scale 1:100 @ A3

Revision 1
Date 15/10/2026
File No. **26173**

**Sheet No.**
**1**




**Benchtop Colour:**

30mm square edge Tristone

**Main Joinery Colour:**

Back Wall & Island Back Panels

**Feature Joinery Colour**

Island, Boxed Ends & Overheads

**Handles:**


4062-192/320-Titanium Grey

**Sink:**

Lazio NZLSS-5545 Stainless Single Bowl


| | | | | | | |
|---|---|---|---|---|---|---|
| signer: Sarah Molyneux | Date: 13 May 26 | Client: Oakridge Homes | BC Ref: Job | Site Address: | Job#: Default | TRENDS KITCHENS |
| g: Kitchen Plan | Scale: 1 : 25 | Customer: The Maple - Selwyn | | | | |

is an original design and must not be released or copied unless applicable fee has been paid or job order placed. All dimensions and size designations given are subject to verification on job site and adjustment to fit job conditi





| Designer: | Date: | Client: | BC Ref: | Site Address: | Job#: |
|---|---|---|---|---|---|
| Sarah Molyneux | 13 May 26 | Oakridge Homes | Job | | Default |
| Drawing: Kitchen Elevation | Scale: 1 : 20 | Customer: The Maple - Selwyn | | | |

is an original design and must not be released or copied unless applicable fee has been paid or job order placed. All dimensions and size designations given are subject to verification on job site and adjustment to fit job conditi





| | | | | | | |
|---|---|---|---|---|---|---|
| signer: Sarah Molyneux | Date: 13 May 26 | Client: Oakridge Homes | BC Ref: Job | Site Address: | Job#: Default | TRENDS KITCHENS |
| g: Kitchen Elevation | Scale: 1 : 20 | Customer: The Maple - Selwyn | | | | |

is an original design and must not be released or copied unless applicable fee has been paid or job order placed. All dimensions and size designations given are subject to verification on job site and adjustment to fit job conditi




| | | | | | | |
|---|---|---|---|---|---|---|
| signer: Sarah Molyneux | Date: 13 May 26 | Client: Oakridge Homes | BC Ref: Job | Site Address: | Job#: Default | TRENDS KITCHENS |
| g: Kitchen 3D Perspective | Scale: | Customer: The Maple - Selwyn | | | | |


is an original design and must not be released or copied unless applicable fee has been paid or job order placed. All dimensions and size designations given are subject to verification on job site and adjustment to fit job conditi




| | | | | | | |
|---|---|---|---|---|---|---|
| Designer: Sarah Molyneux | Date: 24 Feb 23 | Client: Oakridge Homes | BC Ref: Job | Site Address: | Job#: Default | TRENDS KITCHENS |
| Dwg: Pantry Plan | Scale: 1 : 20 | Customer: The Maple - Pantry V2 | | | | |


This is an original design and must not be released or copied unless applicable fee has been paid or job order placed. All dimensions and size designations given are subject to verification on job site and adjustment to fit job conditions.





| Designer: | Date: | Client: | BC Ref: | Site Address: | Job#: |
|---|---|---|---|---|---|
| Sarah Molyneux | 24 Feb 23 | Oakridge Homes | Job | | Default |
| Dwg: | Scale: | Customer: | | | |
| Pantry Elevation | 1 : 20 | The Maple - Pantry V2 | | | |

This is an original design and must not be released or copied unless applicable fee has been paid or job order placed. All dimensions and size designations given are subject to verification on job site and adjustment to fit job conditions.



| | | | | | | |
|---|---|---|---|---|---|---|
| Designer: Sarah Molyneux | Date: 24 Feb 23 | Client: Oakridge Homes | BC Ref: Job | Site Address: | Job#: Default | TRENDS KITCHENS |
| Dwg: Pantry 3D Perspective | Scale: | Customer: The Maple - Pantry V2 | | | | |

This is an original design and must not be released or copied unless applicable fee has been paid or job order placed. All dimensions and size designations given are subject to verification on job site and adjustment to fit job conditions.




SMART SYSTEMS
*Electricians for smart, sustainable homes*

| | | | |
|---|---|---|---|
| **Client Name:** | Oakridge Homes | **Date:** Revised 14-07-2026 | **Designed By:** Mike Lew |
| **Site Address:** | The Maple V7 (Garage Left) | **Plan:** Electrical & Lighting with Elba Pendants | **Phone:** 03 338 4238 |
| **Acceptance Signature & Date:** | | | **Email & Web** info@smartsystems.net.nz smartsystems.net.nz |

# Plan: Option C - Elba - The Maple V7 (Garage Left) - Electrical Design

## Electrical

| | Item | Total |
|---|---|---|
| SWB/MB | Electrical Base with 34-Way Deep Combined Meter Switchboard (Single Phase) | 1 EA |
| R | Rangehood Single Switched Power Socket | 1 EA |
| Fridge | Tradesave Slim Single Power Socket (White) 10A - Fridge | 1 EA |
| MO | Tradesave Slim Single Power Socket (White) 10A - Microwave | 1 EA |
| | Tradesave Double Power Socket Horizontal (White) 10A | 20 EA |
| C | Protective Capping for Socket Electrical in Joinery | 1 EA |
| O | Tradesave Slim Double Power Socket with Oven Isolator Switch (White) 10A | 1 EA |
| H | Tradesave Slim Double Power Socket with Hob Isolator Switch (White) 10A | 1 EA |
| O | Tradesave Built-In Oven Hard-Wired Power Connection up to 20A (max) | 1 EA |
| H | Tradesave Slim Electric Hob Hard-Wired Power Connection up to 32A (max) | 1 EA |
| D | Tradesave Slim Dishwasher Power Socket (White) | 1 EA |
| | Tradesave Garage Door Open/Close Press Switch (White) | 1 EA |
| D | Tradesave Slim Garage Door Power Socket (White) | 1 EA |
| EV | Electric Vehicle Single Phase Future Charging Circuit & Isolator with Blank Wall Plate | 1 EA |
| H | Voltex Hot Water Cylinder Isolator with Lock-Out Capability & Circuit | 1 EA |
| 20 | Air Conditioning Circuit 20A MCB Installation For Heat Pump Circuit | 1 EA |
| | Orca OM866S-10RF Wireless Interconnected Smoke Detector - Photoelectric 10-year battery life | 7 EA |
| | Newtech ST65 Towel Rail 5-Bar Square Ladder 530 x 600mm (Chrome) - Excludes Circuit & Installation | 2 EA |
| T | Tradesave Slim Heated Towel Rail Circuit & Installation (Excludes supply of Towel Rail) | 2 EA |
| E | Extractor Fan Inline 150mm with up to 6m of Duct | 3 EA |
| | Extractor Fan External Grille (White) | 3 EA |
| S | External 180° Infrared Movement Surface Mounted Sensor Up to 12M Range, Adjustable10sec - 15min time delay (White) | 1 EA |

## Electrical

| | Item | Total |
|---|---|---|
| | Recessed Downlight Vynco Lopez 8-Watt (Switchable 3K-4K-5.7K) White Fascia & Circuit | 29 EA |
| Elba | Pendant Light "C" - Elba 365mm with 8-watt LED Lamp (Black) & Circuit | 2 EA |
| | Bulkhead Wall Light Robus Ohio LED 12W IP54 Oval Bulkhead c/w White & Black Trims & Circuit | 1 EA |
| W | Tradesave Slim Light Switch 1-Gang (White) | 13 EA |
| W | Tradesave Slim Light Switch 2-Gang (White) | 3 EA |
| W | Tradesave Slim Light Switch 3-Gang (White) | 2 EA |
| IP | Excel Life White IP Rated Light Switch 1 Gang | 1 EA |
| IP | Excel Life White IP Rated Light Switch 3 Gang | 1 EA |
| 2WY | 2-Way Light Circuit | 2 EA |
| INT | Tradesave Slim 3-way Intermediate Switching Light Circuit | 1 EA |
| Smart Wiring Fibre Hub | Smart Wiring Base 20" Hub 12-Port with Fibre Optic Pathway and Power Circuit - Excludes TV cabling | 1 EA |
| Data 2 | Tradesave Slim Dual Data Sockets RJ45 Ethernet/Internet (Cat6) - White | 1 EA |


# In the Area

## About Arbor Green

Arbor Green has everything that makes up a flourishing neighbourhood. Streets, landscaping and amenities that have been purposefully designed to bring people together and enhance everyday wellbeing.

Once complete, Arbor Green will have 1200 new homes built, a primary school and a central neighbourhood precinct that create two main gathering points, while multiple parks, pathways and cycleways ensure every resident can get around with safety and ease.





## Rolleston and Surrounding Areas

Living in Arbor Green provides you with an open gateway to everything the Selwyn region has to offer.

Rolleston is Canterbury's second largest urban centre. Home to growing businesses, purpose-built facilities, high quality schools and a bevy of shops and eateries, life here is vibrant, easy and fun.

You'll be close to all those urban conveniences that make life easy. There are plenty of work and education opportunities nearby and Christchurch is just 20 minutes down the road. Head a little further afield and Canterbury's mountains, lakes and beaches are yours to discover.



**P:** (03) 977 2832
**E:** info@oakridgehomes.co.nz
**oakridgehomes.co.nz**

OAKRIDGE HOMES

# Why Choose an Oakridge Home?

Oakridge Homes is a locally owned Canterbury company with decades of experience. We are Canterbury's second largest residential builder delivering 200 homes per year with a proven track record of completing over 400 homes for happy homeowners in the region. Oakridge is a small team of fifteen, each of us working diligently to achieve the company goal of delivering quality homes as efficiently and stress free as possible.

All Oakridge house and land packages are competitively priced offering true value for money including turnkey funding, meaning you pay a 10% deposit and the balance the day you get your keys. In our experience this is the preferred contract method when securing finance and a service we offer as a standard inclusion. We work closely with our contractors and suppliers to get the best product for the best cost which is reflected in our all-inclusive package pricing.

At Oakridge we are extremely proud of the relationships we have built with local tradesmen and suppliers, ensuring quality is delivered every time. We deal with one longstanding company per element of the build which has helped us achieve our average build time of 17 weeks. We are very thankful to everyone who makes an Oakridge home come to life, many of us working alongside one another for over ten years.

Our team has put immense effort in to streamlining the consenting process by working alongside the local councils and have formed great relationships with the team leaders guaranteeing our consents are handled as efficiently as possible. Oakridge has a reputation for providing quality documentation for our consent applications which helps ensure we receive your building consent in a timely manner.

We understand that customers value quality and transparency which has been a major focus for Oakridge Homes, we offer a range of fixed price turnkey house and land packages that suit the majority of homebuyers. From the letterbox numbers to the window coverings – an Oakridge home truly is fully inclusive and move in ready when handover day comes. There are no hidden surprises and nothing for you to do but sit back and trust us to build your home.

## Oakridge Homes has taken steps to ensure your home is here to stand the test of time by including:

- Master Build 10-Year Guarantee
- 1 year warranty period
- Exceeds Healthy Homes Standards
- LVL framing (laminated veneer lumber) more durable and less likely to warp
- RibRaft foundation system
- Quality cladding options
- Thermally broken window joinery
- Increased carpet underlay thickness
- Tri-Stone benchtops for easy maintenance
- Full height kitchen joinery to avoid dust collection
- Full length tiled splashback to kitchen
- Bosch appliances
- Exposed aggregate driveways and patios
- Insulated garage and garage door

**P:** (03) 977 2832
**E:** info@oakridgehomes.co.nz
**oakridgehomes.co.nz**

OAKRIDGE HOMES

OAKRIDGE HOMES

# The Oakridge Journey

Decide which house and land package is suitable for you and will meet your needs

Sign your contract and enter your due diligence period (usually 10 working days)

Your solicitor will guide you during this time

**Go unconditional, congratulations!**

In the background we will be preparing your home to be lodged into consent, some time may pass but rest assured everything is going to plan

**Consent granted! A milestone achieved**

Your new home will be scheduled into our build programme

We instruct the works to commence onsite, let's dig some ground!

You will receive updates throughout the construction of your home

17 weeks pass by – that went quick! Your home is ready for the **final inspection**

We will undertake our quality audits and ensure all works are on track to be completed prior to settlement

Code Compliance has issued, your settlement date is now set

During this time you will have your **pre-settlement inspection** to view your home and raise any questions

All works are confirmed as complete and your handover date is organised where you will receive your keys along with other helpful information – an exciting day!

**Thank you for trusting Oakridge Homes it's a privilege to have been chosen as your builder!**

If you'd like more information on one of our listings or want to learn more about the process of buying an Oakridge home, get in touch.

**P:** (03) 977 2832
**E:** info@oakridgehomes.co.nz
**oakridgehomes.co.nz**